


NOTES:

1. THE CONTRACTOR SHALL COMPLY WITH REQUIREMENTS OF THE FLORIDA TRENCH SAFETY ACT.
2. INITIAL BACKFILL SHALL BE HAND PLACED TO 12" ABOVE THE PIPE. BACKFILL SHALL BE MECHANICALLY TAMPED TO A MINIMUM OF 98% OF MAX. DENSITY AS DETERMINED BY AASHTO METHOD T-180.



STANDARD UTILITY DETAILS
 City of Stuart
 Utilities & Engineering Department
 121 S.W. Flagler Avenue, Stuart, Florida 34994

TYPICAL TRENCH CONSTRUCTION

DATE:	OCTOBER 2021	SHEET NUMBER
FILE NAME:	2021 COS Std Details.dwg	10