


SECTION VIEW

NOTES:

1. CONCRETE WET WELL SECTIONS SHALL BE CONNECTED BY STEEL STRAPS. CONTRACTOR SHALL SUBMIT METHOD TO CITY OF STUART UTILITIES & ENGINEERING DEPARTMENT FOR APPROVAL ALONG WITH SHOP DRAWINGS.
2. SEE TYPICAL LIFT STATION DETAILS FOR ADDITIONAL DESIGN AND CONSTRUCTION STANDARDS.
3. BUOYANCY CALCULATIONS SHALL BE SUBMITTED TO THE CITY FOR REVIEW. DESIGN CRITERIA SHALL BE BASED ON DEPTH OF GROUNDWATER AT FINISHED GRADE ELEVATION.



STANDARD UTILITY DETAILS
 City of Stuart
 Utilities & Engineering Department
 121 S.W. Flagler Avenue, Stuart, Florida 34994

LIFT STATION TREMIE POUR	
DATE: OCTOBER 2021	SHEET NUMBER
FILE NAME: 2021 COS Std Details.dwg	56