


**NOTES:**

1. THE CONTRACTOR SHALL COMPLY WITH REQUIREMENTS OF THE FLORIDA TRENCH SAFETY ACT.
2. INITIAL BACKFILL SHALL BE HAND PLACED TO 12" ABOVE THE PIPE. BACKFILL SHALL BE MECHANICALLY TAMPED TO A MINIMUM OF 90% OF MAX. DENSITY AS DETERMINED BY AASHTO METHOD T-180.

**TYPICAL TRENCH DETAIL**



**STANDARD UTILITY DETAILS**  
**City of Stuart Public Works Department**  
 121 S.W. Flagler Avenue, Stuart, Florida 34994  
 (772) 288-5300

**TYPICAL TRENCH  
 DETAIL**

**DATE:** OCTOBER 2016  
**FILE NAME:** 2016 COS Std Details.dwg

**SHEET NUMBER**  
**9**